

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21490-00-00  
Spot: SWSENESE Sec/Twnshp/Rge: 4-30S-22W  
1450 feet from S Section Line, 429 feet from E Section Line  
Lease Name: CHARLOTTE Well #: 1-4  
County: CLARK Total Vertical Depth: 5512 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	611		

179.14

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2009 11:30 PM  
Plug Co. License No.: 34317 Plug Co. Name: BEREDCO LLC  
Proposal Rcvd. from: KAMERON WILSON Company: BEREDCO LLC Phone: (316) 265-3311

Proposed Plugging Method: 1ST PLUG AT 1480' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 12/08/2009 2:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

\*\*BOTTOM JOINT OF 8 5/8" FELL DOWN THE HOLE TO 1360'.\*\* 1ST PLUG AT 1350' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 75 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

INVOICED  
DATE 1-27-10  
INV. NO. 2010060732

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED  
DEC 15 2009  
KCC WICHITA

District: 01

Signed

*Steve Durrant*

(TECHNICIAN)

RECEIVED  
DEC 14 2009  
KCC DODGE CITY

PKS