

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20687-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 35-8S-18W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: DECHANT Well #: 1
County: ROOKS Total Vertical Depth: 3455 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	125 SX
T1	2.375	3430		112.29
PROD	4.5	3454	0	225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2009 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Old production perms: 3133' - 3434'.
Prior operator set CIBP at 2830'.
Bad casing 960' to 1350'.
Cleaned out to 1640' - unable to get down.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2009 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1640'. Allied pumped 100 sxs 60/40 pozmix - 4% gel neat.
Pulled to 840'. Allied pumped 85 sxs cement with 200# hulls - cwc.
PTOH. Squeezed 4 1/2" casing with 25 sxs cement.
Max. P.S.I. 400#. S.I.P. 250#.
Hooked up to backside and pumped 15 sxs cement.
Max. P.S.I. 250#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3404	3434		ARBUCKLE
3233	3253		LANSING

INVOICED
DATE 2-1-10
INV. NO. 2010060740

RECEIVED
DEC 21 2009

Remarks: ALLIED CEMENTING COMPAY-TICKET #33702.

KCC WICHITA

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

DEC 18 2009

