

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21240-00-00
Spot: S2SE Sec/Twnshp/Rge: 10-6S-26W
650 feet from S Section Line, 1320 feet from E Section Line
Lease Name: BEVERLY TEEL Well #: 10-1
County: SHERIDAN Total Vertical Depth: 3930 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	284		200 SX CMT

127.73

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/14/2009 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BERNIE Company: IA OPERATING, INC. Phone: (316) 721-0036

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 09/14/2009 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 2200' w/25 sxs.
2nd. Plug at 1450' w/100 sxs.
3rd. Plug at 330' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 2-1-10
INV. NO. 2010060742

RECEIVED
DEC 21 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Case Morris
(TECHNICIAN)

DEC 17 2009

PCJ