

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24696-00-00
Spot: SENWNENW Sec/Twnshp/Rge: 35-16S-25W
380 feet from N Section Line, 1780 feet from W Section Line
Lease Name: HORACEK Well #: 1
County: NESS Total Vertical Depth: 4590 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		WITH 150 SX CMT
PC		1874		WITH 155 SX CMT <u>149.18</u>
PROD	5.5	4589	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2009 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: VAL DREHER Company: JOHN O. FARMER Phone: (785) 483-8356

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP GEL SPACER THEN 35 SX CMT & HULLS. PULL TO ANHYDRITE & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF IT WILL TAKE.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2009 12:05 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4505' & 18 SX GEL, 35 SX CMT & 150# HULLS. PULL TBG TO 1800' & PUMP 160 SX CMT. CIRCULATED TO SURFACE. PULL TBG & TOP OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMP 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4499	4505		

INVOICED
DATE 2-1-2010
INV. NO. 2010060743

Remarks: USED 60/40 POZMIX 4% GEL BY QULAITY OIL WELL CEMENTING.

Plugged through: TBG

RECEIVED
DEC 18 2009
KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
DEC - 3 2009

KCC DODGE CITY

Form CP 2008