

#35.

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02492-00-01
Spot: SESWNE Sec/Twnshp/Rge: 14-12S-18W
2841 feet from S Section Line, 1662 feet from E Section Line
Lease Name: JOY C Well #: 2
County: ELLIS Total Vertical Depth: 950 feet

Operator License No.: 6600
Op Name: KARST, DON WELL SERVICE, INC.
Address: PO BOX 863
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF		0		
SURF	8.625	195	0	125 SX CMT
PROD	5.5	3686	0	260 SX CMT

Well Type: SWD UIC Docket No: D14309.0 Date/Time to Plug: 12/14/2009 9:30 AM
Plug Co. License No.: 6600 Plug Co. Name: KARST, DON WELL SERVICE, INC.
Proposal Rcvd. from: MONTY KARST Company: KARST, DON WELL SERVICE, INC. Phone: (785) 483-9112

Proposed Plugging Method: Ordered 170 sxs 60/40 pozmix - 4% gel - 500# hulls.
Tiger Wireline Service perf at 170'.
Original TD 3705'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2009 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Karst Well Service RIH with tubing to 950'.
Quality rigged to tubing - pumped 120 sxs cement with 500# hulls mixed into circulate cement to pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 20 sxs cement.
Max. P.S.I. 200#. S.I.P. 150#.
Rigged to 8 5/8" - pumped 10 sxs cement - backside cement came to surface at head.

Perfs:

Top	Bot	Thru	Comments
898	938		

INVOICED

DATE 2/1/10

INV. NO. 2010 060744

RECEIVED

DEC 21 2009

KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3595.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

CM

W. H. GRAHAM

#2

JOY C

Arb

14-12-18W
SE SW NE

Contr. SHAWVER-GRAHAM, INC.

ELLIS

County

E2153

Comm. 10-5-48

Comp. 12-21-48


IP

120 BOPD

Tops	Depth	Datum
ANH	1395	+758
ARB	3668	-1515
T.D.	3676	-1523

Casing

8" 195 600' 01H/5 HRS
5" 3668 ACID 1000
SWB 7½ BOPH/8 HRS



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS