

4-041559

1-19

D-25,325

API number: 15-065-22,004

TO:

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

NE SE NE /4 SEC. 14, 10 S, 21 W
1650 feet from N section line
330 feet from E section line

Operator license# 5135Lease Acheson well # 10Operator: John O. FarmerCounty Graham

Address: P.O. Box 352
Russell, Kansas 67665

Well total depth 3940 feet
 Conductor Pipe: 0 inch @ 0 feet
 Surface pipe 8 5/8 Inch @ 216 feet
 w/150 sxs.

128.05

Aband. oil well __, Gas well __, Input well __, SWD X, D & A __Plugging contractor: Allied Cementing License# -Address: Russell, Kansas 67665Company to plug at: Hour: 9:00A.M. Day: 19 Month: January Year: 94Plugging proposal received from: Duane EichmanCompany: John O. Farmer

Phone: _____

Were: 5 1/2" casing set @ 3873' w/150 sxs. cement. Perf. @ 3873' -
3961'. Perfs salt @ 2300' - Anhy. @ 1750' - Dakota @ 960' - T.O.F. @ 1200'.
Ordered 100 sxs. common with 1/4# F.C. plus 325 sxs. 60/40 pozmix - 10%
gel with 1/4# F.C. plus 500# hulls.

RECEIVED
 STATE CORPORATION COMMISSION

Plugging Proposal Received by: Dennis HamelPlugging operations attended by agent? All[X], Part[], None[]Completed: Hour: 11:15A.M. Day: 19, Month: January, Year: 94

Actual plugging report: Hooked-up to 8 5/8" S.P. Pumped in 15 sxs.
cement. Max. 1000#. S.I.P. 600#. Hooked-up to 5 1/2" casing.
Pumped in 100 sxs. common with 1/4# F.C. plus 310 sxs. cement with
500# hulls. Max. 700#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD X BAD ____ Anhy. plug: YES X NO ____
 Bottom plug(in place): YES X, CALC ____, NO ____ Dakota plug: YES X, NO ____
 Plugged through TUBING ____, CASING X. Elevation: ____ GL

I did X did not [] observe the plugging.

INVOICED

DATE FEB 02 1994INV. NO. 39849

(agent)

Form CP-2/3