



Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION 1034749
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4419
Name: Bear Petroleum, Inc.
Address 1: PO BOX 438
Address 2: _____
City: HAYSVILLE State: KS Zip: 67060 + 0438
Contact Person: Dick Schremmer
Phone: (316) 524-1225
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. ~~15~~ - 15-015-22021-00-00
Spot Description: NW NW NE NW
NW NW NE NW Sec. 3 Twp. 26 S. R. 5 East West
5,191 Feet from North / South Line of Section
3,658 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Butler
Lease Name: WILKINSON Well #: 1
Date Well Completed: 04/24/1982
The plugging proposal was approved on: 04/17/2009 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Plugging Commenced: 12/03/2009
Plugging Completed: 12/04/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	205	0
		Production	4.5	2649	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dumped sand from 2602-2520 and dump bailed 4 sax cement. Ran poly to 260' from surface, pumped 160 sax cement, and circulated to surface. Shut down. Next day - Cut off braden head, mixed and pumped 30 sax, and filled 4 1/2 & 8 5/8 with cement.
Job complete.
Total cement - 194 sax

RECEIVED
JAN 27 2010
KCC WICHITA

Plugging Contractor License #: 3004 Name: Gressel Oilfield Service, Inc.
Address 1: PO BOX 607 Address 2: _____
City: BURRTON State: KS Zip: 67020 + 0607
Phone: (620) 463-5161
Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.
State of Kansas County, Sedgwick, ss.
R. A. Schremmer, President Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202