

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

15-159-19210-00-01

OPERATOR: License #: 33725
Name: Foundation Energy Management, LLC
Address 1: 14800 Landmark Blvd, Suite 220
Address 2: _____
City: Dallas State: TX Zip: 75254 + 1434
Contact Person: David Koss
Phone: (918) 585-1650
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: 14,375
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 159-19210-0001
Spot Description: _____
C- SW 12 SW. SW Sec. 12 Twp. 18 S. R. 10 East West
330 3/7 Feet from North / South Line of Section
4620 4713 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rice
Lease Name: Anna Habiger Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: January 15, 2010 (Date)
by: Steve Van Gieson (KCC District Agent's Name)
Plugging Commenced: January 20, 2010
Plugging Completed: January 21, 2010

Handwritten notes:
Steve Van Gieson
1/14/10
KCC

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle - 3277'-3669'	Water		8-5/8"	195'	none
			4-1/2"	3277'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set plug at 3050'. Dumped 2 sx cement on top of plug. Perforated casing @ 1200', 850', and 250'. Ran 2-3/8" tubing to 1200' and spotted 50 sx, then pulled tbg to 850'. WOC. Tagged plug by wireline. Spotted 50 sx at 850'. Pulled tbg up to 250', circulated cement to surface. Next day topped off backside with cement. Plugging complete.

RECEIVED
JAN 27 2010

Plugging Contractor License #: 7868 Name: Kizzar Well Service KCC WICHITA
Address 1: 320 Frontage Rd Highway 56 Address 2: _____
City: Chase State: KS Zip: 67524 + _____
Phone: (620) 938-2555
Name of Party Responsible for Plugging Fees: Foundation Energy Management, LLC
State of Kansas County, Rice, ss.
David Koss Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Handwritten signature: [Signature]