

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Herman Geo. Kaiser,

Complete Address: 909 Palace Building,, Tulsa, Oklahoma.

Lease Name: Conness Well No. C-2

Location: SE-NE-SE Sec. 22 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3870' Oil Well X

Gas Well      Input Well      GWD Well      D & A      Lost Hole     

Mr. Clark was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3869'--4 1/2" Production casing cemented on bottom with 150 Sx. Top perforations @ 3712'. DV Tool set @ 1780' with 180 Bbl. Chem-Pak.

Sand well back to 3675' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 30 sack gel plus 5 sacks gel and 130 Sx. cement staged.

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 18 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

Very truly yours,

W. L. Nichols  
 Conservation Division Agent