

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
28-1971
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Griffith Well No. B-1

Location: 1320' FSL & 990' FEL-SE Sec. 15 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3755' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 650'.

Circulate hole with heavy mud. Pull DP to 875' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent