

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name: Riedel Well No. D-1

Location: CSE-SE Sec. 6 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4055 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Barnes was instructed to plug the well as follows:

148'--8 5/8" Surface pipe, cement circulated with 75 Sx.
3958'--5 1/2" Production casing cemented on bottom with 100 Sx. Well
plugged back to 3930'. Top perforations @ 3854'.

Sand well back to 3825' and set 5 Sx. cement with dump bailer. pull 5 1/2"
casing and squeeze well with 30 sacks gel with 5 sacks of hulls in initial
gel plus 130 Sx. cement staged.

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1968
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

W. B. Nichols
Conservation Division Agent