

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 2 Twp. 10 Rge. 22 (E) (W)

Location as "NE/CNW/SW" or footage from lines C N/2 N/2 NE/4

Lease Owner Leslie Oil Company

Lease Name Brassfield Well No. 5

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 5-15-62 19

Plugging completed 5-16-62 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3812 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains data for 8-5/8" and 4-1/2" casing.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3812', sanded to 3790' and dumped 4 sacks of cement @ 3790' with dump bailer. Pulled 4 1/2" casing to 500' and circulated with mud. Pumped in 20 sacks of cement. Pulled 4 1/2" casing to 300' and pumped in 20 sacks of cement. Bailed fluid to 35', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED STATE CORPORATION COMMISSION 5-28-1962 MAY 28 1962 CONSERVATION DIVISION Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss. Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 1962

My commission expires May 20, 1964 Milton J. Volin Notary Public.

15-065-03046-00-00

WELL LOG

OPERATOR: K & E, BROWN & FORTIER
719 Union Center Building
Wichita 2, Kansas

FARM NAME: #5 BRASSFIELD
LOCATION: CN/2 S/2 NE/4
Section 2-108-22W
Graham County, Kansas

CONTRACTOR: K & E DRILLING, INC.
719 Union Center Building
Wichita, Kansas

COMMENCED: 5-20-57
COMPLETED: 5-29-57

CASING: 8-5/8" @ 220' (150 sx)
4-1/2" @ 3000 (100 sx)

PRODUCTION: OIL - Lansing

R.T.D. 3800'

ELEVATION: 2321' KB
2318' DF

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Sand & Shale	100
Shale	228
Shale & Shells	810
Sandy Shale	1310
Sand	1530
Red Bed	1580
Red Bed & Shale	1790
Anhydrite	1835
Shale & Shells	2200
Lime & Shale	3075
Lime	3210
Lime & Shale	3400
Lime	3525
Lime & Shale	3550
Lime	3800
R.T.D.	3800

RECEIVED
STATE CORPORATION COMMISSION
5-15-1962
MAY 15 1962
CONSERVATION DIVISION

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Dale Silcott of the K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the log of the #5 BRASSFIELD 'A' Well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 11th, day of June, 1957

Patricia M. Edwards
Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

