

15-065-03044-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 2 Twp. 10 Rge. 22 (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE NE NW

Lease Owner Specter Pipe & Supply, Inc.

Lease Name Brown Estate Well No. B #1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 9-1-56 19

Application for plugging filed Feb 21, 1968 19

Application for plugging approved Feb. 21, 1968 19

Plugging commenced 3/4 1968

Plugging completed 3/9 1968

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Unknown 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Kansas City Depth to top 3572 Bottom 3809 ft. Total Depth of Well 3812 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	226 ft.	none
				4 1/2" OD	3812 ft.	984.54 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3500 with sand, 3 sacks of cement.
Pumped 4 sacks hulls 35 sacks mud & 100 sacks cement to top.

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling

Address Rt # 4 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc.


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of March, 1968

[Signature]
Notary Public.

My commission expires May 21, 1971



15-065-03044-00 00


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- K & E DRILLING, INC.
Farm- Brown Estate "B" No. 1

SEC. 2 T. 10 R. 22W
NE NE NW

Total Depth. 3812'
Comm. 8-23-56 Comp. 9-1-56
Shot or Treated.
Contractor. K & E Drlg.
Issued. 8-1-58

County Graham
KANSAS



CASING:
8 5/8" 226' cem w/150 sx.
5 1/2" 3809' cem w/150 sx.

Elevation. 2341' RB

Production, 175 BOPD

Figures indicate Bottom of Formations.

clay & sand	55
clay & shale	105
shale	930
shale & sand	1330
sand	1560
red bed	1815
Anhydrite	1855
shale & shells	2310
lime & shale	3540
lime	3812 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite	1815
Heebner	3533
Toronto	3555
Lansing	3572

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1968
CONSERVATION DIVISION
Wichita, Kansas