


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 2 Twp. 10 Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. SE SE SW
Lease Owner Leslie Oil Co.
Lease Name Callison "A" #2 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-29-59 19____
Plugging completed 8-1-59 19____
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	237'	none
				4-1/2"	3849'	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 1760', hole bridged.
Pushed bridge to bottom, ran 40 gal sand
and dumped 3 sacks of cement with dump
bailer. Pulled 4 1/2" casing, cleared hole
and checked mud to 230', set rock bridge
to 220' and dumped 25 sacks of cement.
Mudded the hole to 40' set 10' rock bridge
and ran 10 sacks of cement to base of
cellar.

8-11-1959
AUG 11 1959
STATE CORPORATION COMMISSION
Wichita, Kansas

PLUGGING COMPLETED

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 1959

Thomas V. Duggs
Notary Public.

My commission expires 9-27-62

PLUGGING
FILE SEC 2 T. 10 R. 22w
BOOK PAGE 51 LINE 24

DRILLERS

LOG

15-065-00583-00-00

OPERATOR: K & E DRILLING, INC.
719 Union Center
Wichita 2, Kansas

FARM NAME: #2 CALLISON 'A'

CONTRACTOR: K & E DRILLING, INC.
719 Union Center
Wichita 2, Kansas

LOCATION: SE SE SW
Section 2-10S-22W
Graham County, Kansas

CASING: 8-5/8" @ 237' (150 sx)
4-1/2" @ 3849' (100 sx)

COMMENCED: 1-16-58
COMPLETED: 1-23-58

R.T.D. 3850'

ELEVATION: 2334' KB

PRODUCTION: OIL - Lansing

FORMATION RECORD

Depths shown indicate bottom of formation encountered

Cellar	8
Soil & Clay	35
Sand & Clay	50
Shale	237
Shale & Shells	1350
Sand & Shale	1580
Red Bed & Shale	1815
Anhydrite	1870
Shale & Shells	2225
Shale & Lime	2680
Lime	2765
Lime & Shale	3437
Lime	3779
Lime & Shale	3850
R.T.D.	3850

RECEIVED
 STATE DEPARTMENT OF REVENUE
 7-15-1959
 JAN 15 1959
 COMMISSIONER'S DIVISION
 WICHITA, KANSAS

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Dale Silcott of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the K & E #2 CALLISON 'A' well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 25th day of January, 1958

Patricia M. Edwards
Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

PLUGGING
 FILE SEC. 2 T. 10 R. 22W
 BOOK PAGE 51 LINE 24

Leslie Oil Co. ---- Callison "A" ---- Day Work

DATE	HOURS	REMARKS
7-29-59	2 hrs	Checked the hole to 1760', hole bridged. Cleaned cellar.
7-30-59	11 hrs	Tried to knock out bridge could not. Halliburton pumped bridge to bottom. Ran 40 gal sand and dumped 3 sacks of cement on bottom. Checked and shot pipe at 3000', worked pipe loose. Set pipe down.
7-31-59	2 hrs	Worked pipe loose (Pulled 75 jts)
8- 1-59	5 hrs	(Pulled 19 jts) Cleared hole and checked mud to 230', set rock bridge to 220' and dumped 25 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECORDED
STATE
8-11-1959
AUG 11
CO. WICHITA, KANSAS

PLUGGING
FILE SEC 2 T 10 R 22W
BOOK PAGE 51 LINE 24