

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 2 Twp. 10 Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C S/2 SE/4 NW/4

Lease Owner The Shallow Water Refining Company

Lease Name Holmes Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 1-28-66 19

Plugging completed 1-30-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 3813 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	247'	None
				4-1/2"	3813'	2488'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to plug-back @ 3782', pushed plug to 3600', sanded hole to 3590' and dumped 3 sacks of cement with dump bailer. Plug did not hold. Pushed another plug to 3600', set rock bridge to 3595', sanded to 3585' and dumped 3 sacks of cement with dump bailer. Pulled 4 1/2" casing to 600' circulated with 19 sacks of gel mud and pumped in 20 sacks of cement. Filled 4 1/2" casing to 240' and pumped 6 sacks of gel mud and 20 sacks of cement. Pulled balance of 4 1/2" casing and pumped in 10 sacks of cement to cap well.

RECEIVED
2-8-1966
FEB 8 1966

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight

(employee of owner) or (owner/operating) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of February, 1966

My commission expires May 20, 1968

Milton J. Volmer
Notary Public.

DRILLER'S LOG

OPERATOR: K & E DRILLING, INC., et al
719 Union Center Building
Wichita 2, Kansas

FARM NAME: #1 HOLMES

LOCATION: CS/2 SE NW, Sec. 2-10S-22W
Graham County, Kansas

CONTRACTOR: K & E DRILLING, INC.
719 Union Center Building
Wichita 2, Kansas

COMMENCED: 4-1-58
COMPLETED: 4-9-58

CASING: 8-5/8" @ 247' (150 sx)
4-1/2" @ 3813' (100 sx)

ELEVATION: 2333' KB
PRODUCTION: OIL - Lansing

FORMATION RECORD


Depths shown indicate bottom of formations encountered.


Surface Soil & Clay	75
Sand	90
Shale	600
Shale & Red Bed	920
Sand & Shale	1330
Sand	1560
Red Bed	1820
Anhydrite	1860
Shale & Shells	2325
Shale & Lime	2550
Lime & Shale	3135
Lime	3260
Shale & Lime	3380
Lime	3505
Lime & Shale	3560
Lime	3815
R.T.D.	3815

RECEIVED
 STATE CORPORATION COMMISSION
 12-1-1965
 CERTIFICATION
 DEC -1 1965
 CONSERVATION DIVISION
 State of Kansas

STATE OF KANSAS }
 } SS:
COUNTY OF SEDGWICK }

I, Dale Silcott, of K & E DRILLING, INC., hereby swear upon oath that the above and foregoing is a true and correct copy of the Driller's Log of the #1 HOLMES well.


Dale Silcott

Subscribed and sworn to before me this 11th day of April, 1958.

Patricia M. Edwards, Notary Public

My commission expires: August 11th, 1958.