

15-065-00733-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham

County. Sec. 2 Twp. 10S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner K. & E. Drilling, Inc.

Lease Name Callison Well No. 1

Office Address 1006 Central Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced November 20 1956

Plugging completed November 26 1956

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3967 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	None
				4-1/2"	3810'	3302'
				Casing perforated from 3704' to 3708'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 3967' to 3685' and ran 4 sacks of cement which filled to 3668'. Mudded the hole to 220', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to 25', set a rock bridge and ran 10 sacks of cement on top. Plugging completed.

Name of Plugging Contractor West Supply Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Dale Silcott (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott, of K & E DRILLING, INC. 719 Union Center Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 1956. Patricia M. Edwards, Notary Public.

My commission expires 11 August 1958.

PLUGGING
FILE SEC 21 T. 10 R. 22W
BOOK PAGE 106 LINE 82

RECEIVED
CORPORATION COMMISSION
1-11-1957
JAN 11 1957

CONSERVATION DIVISION
Wichita, Kansas