

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3-16-1970  
MAR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Stetler of Birmingham-Bartlett Drlg. Co., has this date requested permission to plug the following described well:

Mr. Stetler guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drilling Company,

Complete Address: 300 Kaufman Building, Wichita, Kansas.

Lease Name: Mincks Well No. 2

Location: NW-SW-NE Sec. 25 Twp. 10 Rge. (E)(W)21

County: Graham Total Depth 3727' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Stetler was instructed to plug the well as follows:

158'--8 5/8" Surface casing, cement circulated.

3723'--5 1/2" Production casing cemented on bottom with 125 Sx. Well had been squeezed in the Dakota to surface with 200 Sx. cement. Fluid level in 5 1/2" @ 125'.

Run tubing to bottom of well and displace 10 Sx. cement. Pull tubing out of cement and circulate heavy gel mud. Pull tubing to 800' and displace 50 Sx. cement thru tubing. Pull tubing to 40' and displace 5 Sx. cement thru tubing.

Very truly yours,

Conservation Division Agent