

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

6-15-1964
 JUN 15 1964

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling, Inc this

date requested permission to plug the following described well:

Union Texas Petroleum
 Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum,

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name: Herrold Well No. 5

Location: NW-NW-NW Sec. 25 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3748 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pully was instructed to plug the well as follows:

205' -- 8 5/8" Surface pipe, cement circulated, 3742' 5 1/2"
production casing.

Sand well back to 3730' and set 4 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to
540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 190' &
displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge
@ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent