

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
11-25-1974
NOV 25 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charlie Crow of Charlie Crow Drilling Co., has this date requested permission to plug the following described well:

Mr. Crow guarantees payment of the plugging fee.

Operator's full Name: Sun Oil Company,

Complete Address: 800 Security Life Building, Denver, Colorado.

Lease Name: Diebolt-L-KC Well No. Tract-12, Well #4

Location: SE-SW-NE Sec. 28 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3911' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Crow was instructed to plug the well as follows:

202'--8 5/8" Surface casing, cement circulated.
3706'--5 1/2" casing with unknown amount of cement on bottom. 5 1/2" casing has been squeezed @ 3242' with 50 Sx. cement, @ 1306' with 100 Sx. cement and @ 1017' with 50 Sx. cement. Well plugged back to 3875'. Top perforations from 3625' to 3826'.

Push plug to 3600', sand back to 3575' and set 4 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Dickel
Conservation Division Agent