

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
11-15-1974
NOV 15 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charlie Crow of Charlie Crow Drilling Company has this
date requested permission to plug the following described well:

Mr. Crow guarantees payment of the plugging fee.

Operator's full Name: Sun Oil Company,

Complete Address: 800 Security Life Building, Wichita, Kansas.

Lease Name: Diebolt L-KC Well No. Tract-15, Well #2

Location: NW-NE-SE Sec. 28 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3900 Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Crow was instructed to plug the well as follows:

398'--9 5/8" Surface casing, cement circulated with 250 Sx.
3899'--5 1/2" casing cemented on bottom with 200 Sx. Well plugged back to
3824'. Perforations from 3881' to 3823'.

Sand well back to 3775' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 160 Cu. Ft.
cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent