


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 15 Twp. 10 Rge. (E) 22 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE NE SW
Lease Owner JONES, SHELburne & FARMER, INC.
Lease Name Andreen Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4-13 19 51
Application for plugging filed 4-13 19 51
Application for plugging approved 4-13 19 51
Plugging commenced 4-13 19 51
Plugging completed 4-13 19 51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Never produced 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	175	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

- Hole filled with heavy mud
- Halliburton plug pushed to 170'
- 1/2 sack hulls dumped on top of plug
- 15 sacks cement mixed and dumped on top of hulls
- Hole filled to top with mud
- Second Halliburton plug pushed to 40'
- 1/2 sack hulls dumped on top of plug
- 10 sacks cement mixed and hole filled with same

4-21-1951
APR 21 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to JONES, SHELburne & FARMER, INC.
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
John O. Farmer (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

John O. Farmer
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of April, 19 51

Josephine E. Wray
Notary Public.

My commission expires February 19, 1955

PLUGGING
FILE SEC-15 TWP-10 RGE-22
BOOK PAGE 74 LINE 39

Jones, Shelburne & Farmer, Inc.

Russell, Kansas

CONTRACTOR'S VERIFIED LOG

Operator JONES, SHELBURNE & FARMER, INC Farm Name Andreen Well No 1

Location NE NE SW, Sec. 15-10-22, Graham County

Pool Name Wildcat County Graham State Kansas

Commencement Date April 1, 1951 Completion Date April 13, 1951.

Log of Well

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
0	165	Shale & Sand		
165	1280	Shale & Shells		
1280	1420	Shale & Sand		
1420	1755	Shale & Shells		
1755	1790	Anhydrite		
1790	2365	Shale & Shells		
2365	2500	Shale & Lime		
2500	3580	Lime & Shale		
3580	3740	Lime		
3740	3880	Lime & Shale		
3880	3982	Conglomerate		

PLUGGING
 FILE SEC 15 T 10 R 24
 BOOK PAGE 74 LINE 31

HIT
 STATE
 4-21-1951
 CONS

