

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-22320-00-00

API NUMBER 15-065-22,320

LEASE NAME Griffith

WELL NUMBER #1

4830' Ft. from S Section Line

4130' Ft. from E Section Line

SEC. 15 TWP. 10 SRGE. 22 (S) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 2-8-87

Plugging Completed 2-9-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Williamson Drlg, Inc

ADDRESS 2008 11th Street Great Bend, Ks 67530

PHONE# (316) 793 8229 OPERATORS' LICENSE NO. 4087

Character of Well D/A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? _____

Which KCC/KDHE Joint Office did you notify? _____

Is ACO-1 filed? by operator If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	313'	8 5/8"	313'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Bottom Plug set @ 1830' w/25 sks Cement thru drill pipe; Next Plug @ 980' w/100 sks Cement thru drill pipe; Next plug @ 350' w/40 sks cement thru drill pipe
Next Plug @ 40' w/10 sks Cement thru drill pipe; Rathole w/15 sks. Well
Plugged w/190 sks 60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Williamson Drilling, Inc. License No. 4087

Address 2008 11th Street Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Terry Williamson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Terry Williamson

(Address) _____

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 87

Cheryl B. Gunn
Notary Public

My Commission Expires: 10-6-87



STATE CORPORATION COMMISSION
2-25-1987
FEB 25 1987
Form CP-2
Revised 08-84
Wichita, Kansas

WILLIAMSON DRILLING, INC.

2008-11TH

GREAT BEND, KANSAS 67530

(316) 793-8229

DRILLERS' WELL LOG

Date Commenced: February 3, 1987
Date Completed: February 9, 1987

Williamson Drilling, Inc.
Griffith #1
NE NW NW Sec. 15,
Twp. 10s, Rge. 22w
Graham County, Ks.


Surface Casing: Ran 7 jts New 20# 8 5/8" casing.
Set @ 313'. Cemented w/175 sks. 50/50 poz.,
2% gel, 3% CC.

0 - 1300' Surface Soil Clay & Post Rock
1300 - 1515' Sand & Clay
1515 - 1811' Redbed
1811 - 1849' Anhydrite
1849 - 3125' Shale w/Lime Stringers
3125 - 3526' Lime w/Shale Stringers
3526 - 3531' Carb. Shale
3531 - 3790' Lime w/Shale Stringers
3790 - 3810' Shale & Lime
3810 - 3872' Lime w/Shale Stringers
3872 - 3900' Chert & Dolomite
3900' RTD

A F F I D A V I T


STATE OF KANSAS
 ss.
COUNTY of BARTON

Terry L. Williamson, of lawful age, does swear and state that
the facts and statements herein are true and correct to the best of
his knowledge.


Terry L. Williamson

Subscribed and Sworn to before me this 14th day of April, 1987.

My Commission Expires:
2-25-91


Susan F. Saylor
Public Notary

NOTARY PUBLIC-STATE of KANSAS
SUSAN F. SAYLER
My Appt. Exp. 2-25-91

RECEIVED
STATE CORPORATION COMMISSION
4-15-1987
APR 15 1987
CONSERVATION DIVISION
Wichita, Kansas