

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117  
15-065-22766-00-00

API NUMBER 15-065-22,766  
LEASE NAME Griffith  
WELL NUMBER #3  
1650' Ft. from N Section Line  
330' Ft. from E Section Line  
SEC. 15 TWP. 10 RGE. 22 (E) or (W)  
COUNTY Graham  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 5-31-96  
Plugging Completed 6-3-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.  
ADDRESS 125 N. Market Suite 1000 Wichita, Ks. 67202  
PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well OIL  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on \_\_\_\_\_ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3785'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	214'	none
				4-1/2"	3782'	1523'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3520' and 4 sacks cement. Shot pipe @2745', 2249', 1711', 1523'; pumped 125 sacks cement with 300# hulls, pulled to 250', circulated cement to surface with 100 sacks cement, 60/40 pos, 10 Gel. Pulled rest of casing. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529  
Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.  
STATE OF Kansas COUNTY OF Rice, ss.


Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.  
(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 21 day of June, 1996

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 24 1996  
6-24-1996  
CONSOLIDATION DIVISION  
WICHITA, KS