

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-065-01869-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Hoof L-KC Unit

WELL NUMBER 404W

330 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 9 TWP. 10 SRGE. 23 WWW(W)

COUNTY Graham

Date Well Completed 2-24-55

Plugging Commenced 10-29-84

Plugging Completed 10-30-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 N.W. 58th Street, Okla. City, Okla. 73112

PHONE 405 949-4400 OPERATORS LICENSE NO. 5447

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Input  
Formation L-KC Depth to Top 3672' Bottom 3854' T.D. 3926'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	- - - -	3672	3854	8-5/8"	250'	0'
				5-1/2"	3924'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

10-29-84: Set packer at 3400' and squeezed old L-KC perf. from 3672-3778' w/200 sx 50/50 pozmix + 6 gel and 10# sx Gilsonite. 10-30-84: Released pressure on tubing and pulled tubing & packer. Perfed Anhydrite at 1980' w/4 sh., ran opened tubing to 3400'. Spotted 17 sx gel, pulled to 1983' & spotted 25 sx 50/50 Pozmix + 6% cc & 3% gel. Pulled to 1733' & spotted 6 sx gel; pulled to 1194', and  
(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Dowell License No. RECEIVED

Address 905 E. Ninth, Box 219, Hay, Kansas 67601 STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del Oliver

(Employee of Operator) CONSCIOUSLY

above-described well, being first duly sworn on oath, says: That I have knowledge of all the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Delbert G. Oliver

(Address) 3545 NW 58th St., Okla. City, OK 73112

SUBSCRIBED AND SWORN TO before me this 26th day of December, 19 84

Joseph J. Carter  
Notary Public

My Commission Expires: 6-12-88

Continued:

spotted 115 sx 50/50 Pozmix + 6% cc + 3% gel. Pumped 85 sx cmt  
between 8-5/8" <sup>-5 1/8"</sup> annulus. P & A completed.  
^

JOHNSON "B" NO. 4 WELL

LOCATION: S/2 SW/4 SE/4  
Section 9-108-23W  
Graham County, Kansas  
SPUDDED: 2-11-55  
COMPLETED: 2-22-55

CONTRACTOR and OPERATOR: Birmingham-Bartlett Drilling Co.  
300 Kaufman Building  
Wichita 2, Kansas

SURFACE CASING: 8-5/8" 2 1/2 casing cemented at 250' with 175 sacks cement and 3 cc.

OIL STRING: 5-1/2" casing cemented at 392 1/2' with 150 sacks cement

L O G

(Figures indicate bottom of formation)

0 - 130	Surface hole
250	Shale and shells
1455	Shale, shells and sand
1650	Sand and shale
1940	Shale and shells
1975	Anhydrite
2510	Shale and shells
2650	Broken lime
2775	Lime and shale
2915	Broken lime
3110	Lime and shale
3175	Broken lime
3260	Lime and shale
3300	Broken lime
3370	Shale and shells
3500	Lime and shale
3570	Broken lime
3711	Shale and lime
3926	Lime
3926	Rotary Total Depth

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Johnson "B" No. 4 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

RECEIVED  
STATE CORPORATION COMMISSION  
10-10-1984  
OCT 10 1984

Subscribed and sworn to before me this 23rd day of February, 1955.

Beverly Lussor  
Notary Public

CONSERVATION DIVISION  
Wichita, Kansas

My commission expires October 2, 1958.