

3-22 15-065-2091-0000

6 031515

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
SE NE, SEC. 15, T 10 S, R 22 W/E  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Griffith Well # 1  
County Graham 122.78

Operator: Ritchie Exp Inc  
Name & Address 125 N. Market Suite 1000

Well Total Depth 3778 feet

Wichita, Ks 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 192

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso License Number 6050

Address Chase, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: 22 Month: Mar Year: 19 91

Plugging proposal received from Monty

(company name) Kelso Casing Co. (phone) \_\_\_\_\_

were: 8 5/8 set at 192 w/140 sks. 4 1/2 set at 3777 w/150 sks. PBDT 2477.

Order sand and common cement. Pull pipe. Order 225 sks 65/35 poz 10% gel

500 lbs. hulls. Allied Cement Co

Ran bailer to 1900. Hole open

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:10PM Day: 22 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Bottom cement back to 2477 w/cement circ up backside to

800. Shot off at 800. Recovered 4 1/2 casing. Sq 8 5/8 w/225 sks cement

blend w/500 lbs. hulls mixed into. Max psi 500 lbs. Close in psi 200 lbs.

Plug completed.

RECEIVED  
STATE CORPORATION COMMISSION

APR 4 1991

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-11-91

INV. NO. 31496

*John S.*

Signed Carl Goodrow  
(TECHNICIAN)