

15-065-03379-00-01

4-031993

10-20

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-60,015

SE SW SW /4 SEC. 15, 10 S, 22 W  
330 feet from S section line  
4290 feet from E section line

Operator license# 4767 Lease Griffith "A" well # 1

Operator: Ritchie Exploration, Inc. County Graham

123.83

Address: 125 N. Market - #1000 Well total depth 3810 feet  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 145 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License#    

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 20 Month: October Year: 94

Plugging proposal received from: John Niernberger

Company: Ritchie Exploration, Inc. Phone:    

Were: Order 375 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:30A.M., Day: 20, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 145' w/100 sxs. cwc. 5 1/2" set @  
3808' w/50 sxs. Squeezed at 1240' - 1270' w/25 sxs. - 1517' - 1548'  
w/200 sxs. PBTB 3782'. Critical area control shots at 2250' - 1830'  
and 1000'. Mixed and pumped 300 sxs. cement blend with 400# hulls down  
5 1/2" to Max. P.S.I. 600#. Close in P.S.I. 200#. Mixed and pumped  
8 5/8" - 100 sxs. cement blend with 100# hulls to Max. P.S.I. 200#  
Close in P.S.I. 50#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1994  
11-8-1994  
WICHITA, KANSAS

Remarks:      
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did X / did not [     ] observe the plugging. Carl Goodrow

INVOICED

DATE 11-8-94

INV. NO: 41613

(agent)  
Form CP-2/3