

15-065-20538-00-00
5-1.

6 031358

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D-16,566
E/2 W/2, ^{NE} SEC. 15, T 10S, R 22 W/E^{XX}

TECHNICIAN'S PLUGGING REPORT

3960 feet from S section line
1650 feet from E section line

Operator License # 5198 4767

Lease Name Griffith Well # C 1 SWD

Operator: A. Scott Ritchie

County Graham 139.75

Name & Address 125 N. Market Suite 1000

Well Total Depth 4300 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 173

Abandoned Oil Well Gas Well Input Well SWD Well x D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 1 Month: May Year: 19 90

Plugging proposal received from Bill

(company name) Kelso (phone)

were: 8 5/8" set at 173 w/135 sks. 5 1/2 set at 4030 w/150 sks. O.H.

Order sand and common cement. Pull pipe. Order 225 sks 65/35 poz 10% gel 2% dicel

500# hulls. Allied Cement Co., Wellbrock water trucks.

Plugging Proposal Received by Carl
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 3:15PM Day: 1 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Sanded to 3980 w/5 sks common cement on sand w/bailer.

Recovered 950 of casing. Shots at 2400; 1600; 1200; 950; Squeezed 8 5/8 w/150 sks cement blend w/150# hulls to max psi 1000#. Close in psi 300#. Plug complete.

Remarks:
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-16-90

INV. NO. 28168

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow