

6 030321

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
S/2 SW/4 SE, SEC. 9, T. 10 S, R. 23 W
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name HOOF L-KC Well # 404 W

Operator: CITIES SERVICE OIL & GAS CORP. County GRAHAM

Name & Address 209 E. WILLIAM

Well Total Depth 3926 ^{127.60} feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 250'

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CEM. License Number _____

Address PLAINVILLE KANSAS.

Company to plug at: Hour: PM Day: 30 Month: 10 Year: 19 84

Plugging proposal received from RICK BROWER

(company name) CITIES SERVICE (phone) _____

were: FIRST DAY - SPOT WITH TUBING 280 SX. CEM. WITH 10* GILSONITE/SX.

BELOW BRIDGE PLUG SET AT 3400 - PUMP PRESSURE = 1500* SHUT IN = 500*

SET OVER NIGHT - SECOND DAY TAGGED CEM @ 3400 - SPOT 17 SX. GEL @ 3400 -

25 SX. CEM. ACCROSS PERE'S @ ANHYDRITE @ 1983 - 6 SX. GEL @ 1733 - 110 SX. CEM

FROM 1194 TO SURFACE. Pump 90 SX. CEM. ON BACK SIDE.

50/5002 6 GEL 3 BCC Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 PM Day: 30 Month: 10 Year: 19 84

ACTUAL PLUGGING REPORT AS ABOVE

Remarks: _____
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

DATE 11-15-84
4777

DEC 07 1984 NOV 23 1984
11-13-1984

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. _____
10-30

CONSERVATION DIVISION
Wichita, Kansas

11-9-84
17