

15-065-01849-00-01

8-25

4-041929

E-15,766-000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-97,614A

SW NE SW /4 SEC. 09, 10 S, 23 W
1650 feet from S section line
~~298~~ 3630 feet from E section line

Operator license# 5030

Lease: Hoof LKC Well # 102

Operator: Vess Oil Corporation

County: Graham 128.28

Address: 8100 E. 22nd Street
N. Building #300
Wichita, Kansas 67226

Well total depth 3947 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 218 Feet
W/150 sxs cmt.

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 25 Month: August Year 1997

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: 316-682-1537

Were: 5 1/2" casing set at 3945' w/ 150 sxs cement.
Perfs at 3682' - 3897'. Squeeze at 1966' w/150 sxs cement.
Ordered 200 sxs 60/40 pozmix - 10% gel - 1/4# F.C. plus 500 # hulls, also
ordered 100 sxs common with 1/4# F.C. in cement.

Plugging Proposal Received by: Dennis Hamel - Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 5:00 P.M., Day: 25, Month: August, Year: 1997

Actual plugging report: Milled, drilled and cleaned-out hole to 387' T.D. Went out of casing at 320'. September 12, 1997 - spotted 150 gallons 28% acid. September 15, 1997 - R.I.H. with tubing to perf at 340' - 350' and perf same. R.U. Cementers to spot 110 sxs cement to circulate cement at surface. P.O.O.H. with tubing. R.U. Cementers to 8 5/8" S.P. Pumped 160 sxs 60/40 pozmix - 10% gel at 150# - 200#. Pressure began to build. Pumped additional 40 sxs cement with P.S.I. building to 1000# P.S.I. Job completed.

Remarks:
Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: G.L.

I did [X] / did not [] observe the plugging

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 9-25-97

INV. NO. 49131

9-25-1997
HD