

6 030618

15-065-03160-00-01

R

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1954

NE, SEC. 20, T 10 S, R 23 (W)E

2970' feet from S section line

330 feet from E section line

Lease Name ^{UNIT} DIEBOLT LKC Well # 4-1

County GRAHAM 126.56

Well Total Depth 3894 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 226 4/1500.

TECHNICIAN'S PLUGGING REPORT

Operator License # 6196

Operator: SUN EXP. & PROD. CO.

Name & Address

525 CENTRAL PARK DRIVE

OKLAHOMA CITY, OKLAHOMA

73105

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor HALLIBURTON CMT CO License Number

Address HAYS KANSAS

Company to plug at: Hour: PM Day: 19 Month: 12 Year: 19 85

Plugging proposal received from JOHN HECK

(company name) SUN EXP. & PROD. CO.

were: CIBP @ 3600' w/4SX. COM.CMT. ON TOP. DISPLACE GEL FROM TOP OF CEMENT
TO 1100' - DISPLACE CEMENT MIX. FROM 1100' TO SURFACE. PUMP DOWN
ANNULUS. ORDER 25 SX. GEL 250 SX. GO/4002 GEL 3 1/2" 4 SX.
HULLS.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 3:20 PM Day: 19 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT TAG. CEMENT WITH TUBING PUMP DOWN TUBING 3SX. HULLS
25 SX. GEL DISPLACE FLUID IN HOLE WITH GEL TO 1100' LAY DOWN
TUBING TO 1100' DISPLACE CEMENT MIX. TO SURFACE WITH 1 SX. HULLS
PUMP DOWN ANNULUS W/CMT. MIX. TOTAL CMT. MIX. 250 SX.
PLUG COMPLETE.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (could not observe this plugging.)

DATE JAN 14 1986

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. 12013 12-19

FORM CP-2/3
Rev. 01-84