

15-065-03161-00-00

10-17

6 031443

API NUMBER 15- 1954

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N/2 SE NE, SEC. 20, T 10 S, R 23 W/E

3630 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Lease Name Diebolt Unit Well # 4-2

Operator: Geneva Res. Inc.

County Graham 126.55

Name & Address 50 California St. Suite 930

Well Total Depth 3894 feet

San Francisco, California 94111

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 239

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address Ness City, Ks.

Company to plug at: Hour: PM Day: 17 Month: Oct. Year: 19 90

Plugging proposal received from Gerald Riedel

(company name) Geneva (phone)

were: 8 5/8 set at 239 w/150 sks. 5 1/2 set at 3889 w/175 sks. PBTB 3402. Perfs

3827-73. Shot holes at 1925 anhy. 1100 Kiowa. Well record shows d.v. at 1933. But no

other info but was most likely circ w/cempac. Ordered 300 sks 65/35 poz 10% gel, 500 lbs.

hulls. Halliburton, Sally's water trucks, Express Well Service. Hole open by wireline.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30PM Day: 17 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 2000 mixed and pumped 75 sks thru tubing.

Laid down tubing to 1000 mixed and pumped 125 sks to circ. Laid down tubing. Sq 5 1/2 w/total

210 sks cement blend w/500 lbs. hulls to max psi 500 lbs. Close in psi 200 lbs.

Sq annulus w/90 sks cement blend to max psi 200 lbs. Close in psi 200 lbs. Plug complete.

11-8-1990
NOV 8 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-13-90

INV. NO. 39950

J.S.

Signed Carl Goodnow
Carl Goodnow