

10-16

To: **6 031441**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1954

SE NE NE, SEC. 20, T 10 S, R 23 W/E  
2970 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Lease Name Diebolt Unit Well # 4-3

Operator: Geneva Res. Inc.  
Name & Address 50 California St. Suite 930  
San Francisco, Calif. 94111

County Graham 126.45

Well Total Depth 3891 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 256

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_

Address Ness City, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 16 Month: Oct. Year: 19 90

Plugging proposal received from Gerald Riedel

(company name) Geneva (phone) \_\_\_\_\_

were: 10 3/4 set at 256 w/140 sks. 7" set at 3891 w/175 sks. PBDT 3880. Perfs

3826-70. Placed shot holes at 1925 anhy and 1100 Kowa sh. Ordered 350 sks 65/35 poz

10% gel, 500 lbs. hulls. Halliburton Cement Co. Express Well Service to run pipe.

Sallys water trucks. Cleaned hole with tubing. Small bridge near surface. Ran wireline.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00 PM Day: 16 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 2000. Hole open. Mixed and pumped 100 sks cement

blend w/good circulation laid down tubing to 1000. Mixed and pumped through tubing

100 sks to surface. Laid down tubing. Sq 7" w/total of 220 sks. to max psi 500 lbs.

Close in psi 500 lbs. Sq 10 3/4 w/100 sks to max psi 300 lbs. Close in psi 300 lbs. Plug

complete.

11-8-1990  
NOV 8 1990

Remarks: \_\_\_\_\_ (If additional description is necessary, use BACK of this form.)

**INVOICED**

Observe this plugging.

DATE 11-13-90

INV. NO. 29948

*Jul S.*

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow