

4-031736

8-17
15-065-03158-00-00

123
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1955
S2 SW NE /4 SEC. 20 , 10 S, 23 W
1980 feet from S section line
1650 feet from E section line

Operator license# 30241 Lease Diebolt LKC Unit well # 3-3

Operator: Geneva Resources, Inc. County Graham

Address: Box 2607 Well total depth 3889 feet ^{126.39}
Wichita, Kansas 67201-2607 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 17 Month: August Year: 92

Plugging proposal received from: Frank Brungardt

Company: Geneva Resources, Inc. Phone: _____

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to perms.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:45P.M., Day: 17, Month: August, Year: 92

Actual plugging report: 8 5/8 set @ 255' w/175 sx. 5 1/2" set @ 3887'
w/100 sx. Shots @ 1900' and 1100'. Perf. 3855' - 3880'. P.B.T.D. 3884'.
Plug through tubing. Squeeze 5 1/2" w/250 sx. cement blend w/500# hulls
mixed in to Max. P.S.I. 500#. Close in P.S.I. 150#. Squeeze annulus
w/100 sx. cement blend to Max. P.S.I. 150#. Close in P.S.I. 150#.
Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anyh. plug: YES 1960 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2410

I did / did not observe the plugging. Carl Goodrow

INVOICED
DATE: 8-27-92
NO. 36068

RECEIVED
STATE CORPORATION COMMISSION
8-24-1992
AUG 24 1992
CONSERVATION DIVISION
WICHITA, KANSAS

(agent)
Form CP-2/3