

To: **6 031336**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Operator: Geneva Resources Inc.
Name &
Address 50 California St. Suite 930
San Francisco, California 94111

API NUMBER 15-

SW NW NE, SEC. 20, T 10 S, R 23 W/E
4290 feet from S section line
2310 feet from E section line

Lease Name Diebolt Unit Well # 3-4

County Graham 126.95

Well Total Depth 3906 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well Gas Well Input Well X SWD Well D&A
E 9110

Other well as hereinafter indicated

Plugging Contractor Express Well Service License Number

Address Victoria, Ks.

Company to plug at: Hour: AM Day: 15 Month: Feb Year: 19 90

Plugging proposal received from Gerald Riedel

(company name) Geneva (phone)

were: 8 5/8" set at 223' w/175 sks. 5 1/2" set at 3906' w/125 sks. Perfs 3600 - 3850'.

Shot at 1925 anhy and 1100' Kiowa. Order 225 sks 65/35 poz 10% gel 2% dicel,

50 sks common cement 500# hulls. Halliburton Cement Company. Wellbrock Water Trucks.

Order work string Express Well Service.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:15 P Day: 15 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1995'. Spot 50 sks common cement.
Lay down 13 joints tubing. Circulate to surface w/cement blend w/hulls added.

Lay down tubing. Squeeze 5 1/2#. To mas psi 350#. Close in psi 350# w/total of 150 sks.

Squeeze 8 5/8" annulus w/75 sks to max psi 200#. Close in psi 200#. Plug complete.

Remarks: RECEIVED
Additional description is necessary, use BACK of this form.)

INVOICE
DATE 3-26-90 3-20-1990
27709
2-15

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow