

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20913-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 6-10S-24W  
4840 feet from S Section Line, 3960 feet from E Section Line  
Lease/Unit Name: RIEDEL Well Number: 3  
County: GRAHAM Total Vertical Depth: 4075 feet

Operator License No.: 6622  
Op Name: JASON OIL COMPANY  
Address: PO BOX 701 363 W 12TH ST  
RUSSELL, KS 67665

Conductor Pipe: Size feet: 8/32.44  
Surface Casing: Size 8.625 feet: 208 w/175 sxs cmt  
Production: Size 5.5 feet: 4071 w/275 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/15/2001 12:00 PM  
Plug Co. License No.: 6622 Plug Co. Name: JASON OIL COMPANY  
Proposal Rcvd. from: MIKE Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed Plugging Method: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Order work string.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/15/2001 2:00 PM KCC Agent: CARL GOODROW

**Actual Plugging Report:**

8 5/8" set at 208' w/175 sxs cement. 5 1/2" set at 4071' w/275 sxs cement.  
Prod Perfs 3922' - 3927'; 3982' - 3988'.  
Junk in the hole at 2160'.  
Ran tubing to 2160'. Displaced 50 sxs cement blend.  
Pulled tubing to 1385'. Displaced 50 sxs cement blend.  
Pulled tubing to 935' - circulated w/30 sxs cement blend.  
Topped off with 10 sxs.  
Total 140 sxs with 500# hulls mixed in.  
Squeezed 8 5/8" w/50 sxs cement blend to Max. P.S.I. 100#.  
Held.

Remarks: LEASE READS AS FOLLOWS: 110' S.OF N2N2NW 06-10-24W. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

RECEIVED

OCT 26 2001

KCC WICHITA

OCT 17 2001

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

DATE 10-26-01

AMOUNT 2002060859

EMPIRE DRLG. CO. #3 RIEDEL 6-10-24w  
 SUITE 1750, 125 N. MARKET 440'FNL&  
 WICHITA, KS. 1320'FWL.HW  
 CONTR MURFIN DRLG. CO. CTY GRAHAM

GEOL \_\_\_\_\_ FIELD DREIL SW

2479 KB CM 4/1/77 CARD ISSUED 5/5/77 IP P 50 BOPD, NW  
 LANS 3922-27 &  
 3982-88

API 15-065-20,913

LOG	TOPS	DEPTH	DATUM
ANH		2128	+ 354
B ANH		2162	+ 317
HQW		3526	-1047
OREAD		3687	-1208
HEEB		3742	-1263
TOR		3767	-1288
LANS		3882	-1403
MUNCIE CRK		3906	-1427
BKC		4012	-1533
RID		4075	-1596
LTD		4073	-1594

8-5/8" 208/175sx, 5 1/2" 4071/275  
 DST (1) 3776-93/30-45-30-45, 110' L  
 SIP 915-915# FP 30-529# BHT 118°  
 DST (2) 3819-32/30-30-30-30, 110' L  
 390' GO, W/TR WTR, SIP 346-30  
 40-163# BHT 108°  
 DST (3) 3848-72/30-45-30-45, 200' L  
 SIP 631-610# FP 30-112# BHT 118°  
 DST (4) 3913-30/30-30-30-30, 200' L  
 600' MGCOSW (5% OIL) SIP 346-30  
 FP 25-285# BHT 118°  
 DST (5) 3937-55/30-30-30-30, 200' L  
 F OIL SPKS, SIP 41-31# BHT 108°  
 DST (6) 3954-80/PKR FAILED

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS