

6 030760

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-20,713

SUNESW SEC. 6E, T. 10 S., R. 24 W. 4P

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114

Lease Name Geo. Nickelswell # B-1

Operator: DON E. PRATT

County GRAHAM 133,58

Name & Address P.O. Box 370

Well Total Depth 4110 feet

HAYS, KANSAS

Conductor Pipe: Size _____ feet

67601

Surface Casing: Size 8 5/8 feet 192'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____

Address HAYS, KANSAS

Company to plug at: Hour: PM Day: 1 Month: 7 Year: 19 86

Plugging proposal received from MARVIN MILLER

(company name) DON E. PRATT (phone) _____

were: 8 5/8" SET @ 192' w/150sx. 4 1/2" SET @ 4106' w/150sx. PBTD 4068'

PERF. 3882' - 4046' ORDER SAND & COM. CMT. PULL PIPE ORDER

200SX. ECONOLITE CMT. MIX. & 5SX. HULLS. HALLIBURTON CMT. CO.

COMPANY WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 PM Day: 1 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO PBTD TO 3830' SPOT 4SX. COM.

CMT. ON SAND w/BAILER. SHOT & RECOVERED 1600' OF 4 1/2"

TIE ON TO 8 5/8 MIX. & PUMP 3SX. HULLS 200SX. ECONOLITE + 2SX.

HULLS. MAX. PSI. 950# CLOSE IN 200# PLUG. COMPLETE

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG - 6 1986
INV. NO. 14623

8-4-1986
AUG

Signed Carl Goodrow
(TECHNICIAN)

22
7-30-86