

6 030761

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-20,713
NENWSW
~~SOUTH~~ SEC. 4, T. 10 S, R. 24 (W) 10
2310
1650 feet from S section line
4290
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114

Lease Name GEO. NICKELSON Well # B-2

Operator: DON E. PRATT

County GRAHAM 133.58

Name & Address P.O. Box. 370

Well Total Depth 4110 feet

HAYS, KANSAS

Conductor Pipe: Size _____ feet

67601

Surface Casing: Size 8 3/8 feet 212'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____

Address HAYS KANSAS

Company to plug at: Hour: PM Day: 2 Month: 7 Year: 19 86

Plugging proposal received from MARVIN MILLER

(company name) DON E. PRATT (phone) _____

were: 8 3/8 SET @ 212' w/200sx. 4 1/2 SET @ 4100' w/150sx. PBTD 4061'

PERF. 4015 1/2' - 4058' ORDER SAND & COM. CNT. PUMP PIPE ORDER

200sx. ECONOLITE CNT. MIX. & 5sx. HULLS. HALLIBURTON CNT. CO.

COMPANY WATER TRUCKS

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:PM Day: 2 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3960' SPOT 4sx. COM. CNT.

ON SAND w/BAILER SHOT & RECOVERED 1600' OF 4 1/2"

TIE ON TO 8 3/8 MIX. & Pump 3sx. HULLS 200sx. CNT. MIX. + 2sx. HULLS

MAX. PSI 900# CLOSE IN 150# PLUG. COMPLETE

Remarks: _____

INVOICED

(did / did not) observe this plugging.

DATE AUG - 6 1986

8-4-1986

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 14619

AUG 8 1986