

6 230762

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-20,737-00-00
SESESU SEC. 4, T. 10 S, R. 24 WDR

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114
Operator: DON E. PRATT
Name & Address P.O. Box 370
HAYS, KANSAS
67601

330 feet from S section line
2970 feet from E section line
Lease Name Geo. Nickelson Well # B-3
County GRAHAM 133.58
Well Total Depth 4110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 7/8 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____
Address HAYS, KANSAS

Company to plug at: Hour: PM Day: 1 Month: 7 Year: 19 86

Plugging proposal received from MARVIN MILLER
(company name) DON E. PRATT (phone) _____

were: 8 7/8 SET @ 208' w/165sx. 4 1/2 SET @ 4100' w/150sx. PBTD 4054'
PERF. 3868 - 4042' ORDER SAND & COM. CNT. PULL PIPE ORDER
200sx. ECONOLITE CNT. MIX. + 5 sx. HULLS HALLIBURTON CNT. CO
COMPANY WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3:PM Day: 1 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3800' SPOT 4sx. COM. CNT.
ON SAND w/BAILER SHOT & RECOVERED 1600' OF 4 1/2"
TIE ON TO 8 7/8" MIX. & Pump 3sx. HULLS - 200sx. CNT. MIX. + 2sx. HULLS
MAX. PST. 1400" CHOSE IN 150" PLUG COMPLETE

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG - 6 1986
INV. NO. 14620

8-4-1986
AUG 4

Signed Carl Goodrow
(TECHNICIAN)

70
7-30-86