

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-20,740

5/2 5/2 SW SEC. 4, T. 10 S, R. 24 (W) W

330 feet from S section line

3960 feet from E section line

Lease Name Geo. Nickelson Well # B-4

County GRAHAM 133.74

Well Total Depth 4115 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 3/8 feet 175'

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114

Operator: DON E. PRATT

Name & Address P.O. Box. 370

HAYS, KANSAS

67601

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON License Number \_\_\_\_\_

Address HAYS, KANSAS

Company to plug at: Hour: PM Day: 1 Month: 7 Year: 19 86

Plugging proposal received from MARVIN MILLER

(company name) DON E PRATT (phone) \_\_\_\_\_

were: 8 3/8" SET @ 175' w/165sx. 4 1/2" SET @ 4088' w/150sx. PBTD 4075'

PERF. 3981' & 4054' ORDER SAND & COM. CMT. PULL PIPE ORDER

200SX. ECONOLITE & 5SX. HULLS HALLIBURTON CMT. CO., COMPANY

WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:PM Day: 1 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3930' SPOT 4 SX. COM. CMT.

ON SAND w/BAILER SHOT & RECOVERED 1000' OF 4 1/2"

TIE ON TO 8 3/8 MIX. & PUMP. 3 SX. HULLS - 200SX. CMT. MIX. & 2 SX

HULLS. MAX. P.S.T. 700# CLOSE IN 300# PLUG. COMPLETE.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
DATE AUG - 6 1986  
INV. NO. 14621

8-4-1986  
AUG 4 1986

Signed Carl Goodrow  
(TECHNICIAN)

19  
7-30-86