

6 030765

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114
Operator: DON E. PRATT
Name & Address: P.O. Box 370
HAYS, KANSAS
67601

API NUMBER 15-065-20,791
NE SWSW, SEC. 4, T. 10 S, R. 24 W
3630 feet from S section line
4290 feet from E section line
Lease Name GEA NICKELSON Well # B-6
County GRAHAM 134.23
Well Total Depth 4130 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____

Address HAYS KANSAS

Company to plug at: Hour: PM Day: 2 Month: 7 Year: 19 86

Plugging proposal received from MARVIN MILLER

(company name) DON E. PRATT (phone) _____

were: 8 5/8 SET @ 225' w/150 SX. 4 1/2 SET @ 4110' w/150 SX. PBTD 4078'
PERF. 3989' - 4070' ORDER SAND & COM. CNT. PULL PIPE ORDER
200 SX. ECONOLITE CNT. MIX. & 5 SX. HULLS HALLIBURTON CNT. CO.
COMPANY WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:PM Day: 2 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3930' SPOT 4 SX. COM CNT.
ON SAND w/BAILER. SHOT & RECOVERED 1350' OF 4 1/2 DROPPED 250'
OF 4 1/2 THROUGH SLIPS
TIE ON TO 8 5/8 MIX. & PUMP 3 SX. HULLS - 200 SX. CNT. MIX. + 2 SX HULLS
MAX. PSI. 300# CLOSE IN 150# PLUG COMPLETE.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE AUG - 6 1986
INV. NO. 14617

8-4-1986
AUG 4

Signed Carl Goodrow
(TECHNICIAN)

11
1-30-86