

15-065-21521-00-01

9-18 4-032093

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-21,521  
100' NE of 5  
C SW NW /4 SEC. 04, 10S, 24 W  
3400 feet from S section line  
4520 feet from E section line

Operator license# 4767

Lease: Denio "P" Well # 5

Operator: Ritchie Exploration, Inc.

County: Graham

Address: 125 N. Market  
Suite #1000  
Wichita, Kansas 67202

Well total depth 4130 <sup>134.23</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8% Inch @ 209 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67525

Company to plug at: Hour: P.M. Day: 18 Month: September Year: 1995

Plugging proposal received from: Manny

Company: Mike's Testing & Salvage Phone:     

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order sand and 4 sxs comment cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 25 1995  
9-25-1995  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 1:30 P.M., Day: 18, Month: September, Year: 1995

Actual plugging report: 8 5/8" set at 209' cwc with 175 sxs. 4 1/2" set at 4128' with 200 sxs. Prod. Perfs at 3856' - 4057'. PBD 4077'. Sand back to 3800' with 4 sxs common cement on sand with bailer. First shot at 2250' - second shot recovered 1350' of 4 1/2" casing. Mixed and pumped down 4 1/2" 80 sxs cement blend with 200# hulls to 2250' with 500# P.S.I. Pulled pipe to 150' circulated cement to surface with 40 sxs cement blend, into cellar. Laid down casing. Hole remained full of cement. Plug completed.

Remarks:       
Condition of casing(in hole): GOOD      BAD      Anhy.plug: YES      NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES     , NO       
Plugged through TUBING     , CASING     . Elevation:      GL

I did X did not      observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3

INVOICED  
DATE 10-6-95  
INV. NO. 43678