

4-2

15-065-20809-00-01

17R

4-031803

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-20,809

SW NW NE /4 SEC. 05, 10 S, 24 W  
4290 feet from S section line  
2310 feet from E section line

Operator license# 4767 Lease Gano well # P1

Operator: Ritchie Exploration, Inc. County Graham

Address: 125 N. Market Well total depth 4100 feet <sup>133.25</sup>  
Suite 1000 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 277 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 2 Month: April Year: 93

Plugging proposal received from: David

Company: Kelso Casing Pulling Phone:                     

Were: Order sand and common cement. Plug bottom.  
Order 250 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Allied Cement Co. Bottom checked with bailer.  
8 5/8" set @ 277 w/175 sx. 4 1/2" set @ 4099' w/125 sx.  
Perf. 3830' - 4024'.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 1:00P.M., Day: 2, Month: April, Year: 93

Actual plugging report: Dump sand to 3780' w/4 sx. common cement on  
sand with bailer. Shot @ 2600'. Shot @ 1900' anhy. Pump 100 sx.  
cement blend from 1600' to 2600'. Shot @ 1600'. Pump 75 sx. cement  
blend from 1330' to 1600'. Shot @ 1330' and 1000' recovered 1006'  
of 4 1/2" casing. Pump 25 sx. cement blend, lay down casing to 300'  
Pump 50 sx. cement blend to circulate heavy cement into cellar.  
Lay down casing, cellar and 8 5/8" full of cement. Plug completed.

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1993  
4-13-1993  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Condition of casing(in hole):GOOD X BAD      Anhy.plug:YES X NO       
Bottom plug(in place):YES X, CALC     , NO      Dakota plug:YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL     

I did X / did not [      ] observe the plugging. Carl Goodrow

INVOICED  
DATE 4-19-93  
INV. NO. 375-93

HO

(agent)  
Form CP-2/3