

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
6-5-1964
JUN 5 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil of Kansas,

Complete Address: Box #97, WaKeeney, Kansas.

Lease Name Dreiling Well No. K C-1

Location CSW-SW Sec. 5 Twp. 10 Rge. (E) (W) 34

County Graham Total Depth 4070'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4:00PM Day 29 Month 5 Year 1964

The Above well, was plugged as follows:

219'--8 5/8" Surface pipe, cement circula ted with 175 Sx.
4039'--4 1/2" production casing, cemented with 150 Sx. Well Plugged back
to 4043', top perforations 3875' to 3879'.

Sanded well back to ~~3865'~~ 3865' and set 3 Sx. cement with dump bailer.
Pulled 4 1/2" to 600' and circulated heavy gel mud (17 Sx. gel), and dis-
placed 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 190' and displaced 20 Sx.
cement thru 4 1/2", Pulled 4 1/2", set rock bridge @ 35' and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. D. Nichols
Well Plugging Supervisor

DATE 6/5/64
INV. NO. 9263-4