

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
1-4-1973
JAN 4 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt,

Complete Address Box #370, Hays, Kansas. 67601

Lease Name Elmer Gano Well No. C-1

Location 440' FSL & 440' FWL of NE/4 SW SW NE Sec. 5 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 8:00 AM Day 31 Month 12 Year 1972

The above well was plugged as follows:

221'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1000'

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225' to 900'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 1/4/73
INV. NO. 6814-w