

KANSAS

15-065-20621-00-00  
Form CP-3  
Rev. 6-4-68STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTRECEIVED  
STATE CORPORATION COMMISSION  
8-13-1973  
AUG 13 1973  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt,  
Complete Address P. O. Box #370, Hays, Kansas.  
Lease Name Herman Well No. 1  
Location SE-SE-NW Sec. 9 Twp. 10 Rge. (E) (W) 24  
County Graham Total Depth 4052'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center, Wichita, Kans. License No.         
Operation Completed: Hour 1:00 PM Day 8 Month 8 Year 1973

The above well was plugged as follows:

196'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 925'.Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement  
thru DP from 1150' to 825'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging SupervisorINVOICED  
DATE 8/15/73  
INV. NO. 9956-W