

15-065-20632-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 17 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum, Inc.

Complete Address 300 W. Douglas Wichita, Kansas

Lease Name Pfeifer "H" Well No. 1

Location C NE NW NE Sec. 10 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4050

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling

Address Wichita, Kansas License No.       

Operation Completed: Hour 1:30 A Day 14 Month 9 Year 1973

The above well was plugged as follows:

RTD 4050' 8 5/8 csg set at 248' cwc 150 sx. Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 1000' and displaced 70 sx

cem thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 9-17-73

INV. NO. 7912-W