

15-065-20460-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dane G. Hansen Trust,
Complete Address Box #187, Logan, Kansas.
Lease Name Herman Well No. 1
Location NE-NE-SW Sec. 10 Twp. 10 Rge. (E) (W) 24
County Graham Total Depth 4030'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor C & G Drilling Company,
Address 1107 Union National Bank Bldg., Wichita, Ks. License No.
Operation Completed: Hour 2:00 PM Day 13 Month 7 Year 1971

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 950'. Pulled DP to 215' and displaced 29 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 7-16-71
INV. NO. 4009-W