

KANSAS

✓ STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-23-1971
JUN 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Manz Well No. 4

Location SE-SW-SE Sec. 12 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4016'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 10:45 AM Day 16 Month 6 Year 1971

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.

4013'--5 1/2" Production casing, cemented on bottom with 100 Sx. No plug back. Top perforations @ 3980'.

Sanded well back to 3900' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (2585') and squeezed well initially with 5 sacks hulls and 5 sacks gel. Pressure built to 1400#. Bled well back and squeezed well with 10 Sx. cement. Final shut-in pressure-1000#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 6/23/71
INV. NO. 3900-W