

15-065-20402-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

DEC 31 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Glen N. Rupe and Walter Probst,

Complete Address 222 Brown Building, Wichita, Kansas.

Lease Name Herman Well No. 1

Location NW-NE-SW Sec. 15 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3812'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 7:30 PM Day 28 Month 12 Year 1970

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INDEXED
DATE 12/31/70
INV. NO. 3142-W