

15-065-20744-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

RECEIVED
MAR 22 1976
3-22-76
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Murfin Drilg. Co.
Complete Address 617 Union Center Wichita Kansas 67202
Lease Name Hobbs. Well No. #1
Location SW-NW-SW- Sec. 19 Twp. 10 Rge. 24(E) (W) X
County Graham. Total Depth 3975
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing. Pulling.
Address Box 176 Chase Kansas. License No. 683
Operation Completed: Hour 10:00 AM Day 18 Month March Year 1976

The above well was plugged as follows:

KB. 2406 - Dat Top. 1500' S.P. 89' of 8 5/8" cwc, 100 sx.
Oil String. 4 1/2" set @ 3974 w/175 sx. cem. Plug Back
To. 3921 - Perf. 3861 to 69, 3882 to 84, 3904 to 3910'
Bottom Plug - To 3650 w/sand + 3 sx. cem. cem.
Pumped down. 8 5/8" S.P. 3 sx. Halls, 70 sx. cem. 50/50 poz-
6? Gel., 8 sx. Gel. Release Plug. + 60 sx. cem. 50/50 Pozo 6? Gel.
Closing Pres. 400 lbs. Recovered 3110' of 4 1/2" casing.
Allied Cementing.

I hereby certify that the above well was plugged as herein stated.

Signed: Gilbert Balthezer
Well Plugging Supervisor

INVOICED
DATE 3-29-76
INV. NO. 2935-W